

Wall Reference / approximate length in metres (m)

Reinforced Concrete / Masonry Walls	
1. STONE PIER	583m
2. NOTHE PARADE	527m
3. TRINITY ROAD / COVE ROW	338m
4. NORTH QUAY	214m
5. WESTHAM BRIDGE	84m + 121m
6. WEYMOUTH MARINA	157m
7. COMMERCIAL ROAD	299m + 31m
8. CUSTOM HOUSE QUAY	149m
9. FERRY BERTH 4	143m
10. FERRY BERTH 3	58m
Total	2704m


Sheet Pile Walls	
A. ANGLING CLUB	172m
B. CUSTOM HOUSE QUAY	218m
C. COVE ROW	14m + 26m
D. CUSTOM HOUSE QUAY	78m
E. PENINSULA (SOUTH)	163m
F. PENINSULA (EAST)	167m
G. PENINSULA (NORTH)	339m
Total	1177m

Concrete Pile / Beam Walls	
Ø PLEASURE PIER	195m
Total	195m

Notes

Key to existing walls

- Reinforced concrete / masonry (1-10)
- Sheet pile (A-G)
- Concrete pile / beam (Ø)



Weymouth & Portland  
Borough Council

Assets & Infrastructure

David Brown FRICS,  
Head of Assets & Infrastructure,  
South Walks House,  
South Walks Road,  
DORCHESTER,  
Dorset,  
DT1 1UZ  
Tel: 01305 251010 Fax: 01305 251481

Weymouth  
Weymouth Harbour Walls  
Remediation Project  
Wall Location Plan

Drawn by : DW / PJS	Checked by : RH	Approved by : RH
Date : 10/07/18	Scale : 1 : 5000 (A3)	
Drawing File Reference : Weymouth Harbour Wall Locations 100718.dwg		
Drawing Number :		Rev. :